

# Laboratory Report

**Date** 

26-June-2014

**Customer Shanghai Superhouse Building Material Co Ltd** 

10 Hang Fan Road, Pudong New Area, Shanghai, China

Test No:

AZT0151.14.xls



NATA Accredited Laboratory No: 15147

Azuma Design Pty Limited 52 Justin Street, Smithfield. NSW 2164 Ph 02 9604 0255 E-Mail info@azumadesign.com.au

# **TESTING LABORATORY REPORT**



Reported Nathan Olsen by:

Checked Robed Irwin by:

NATA Accredited Laboratory No: 15147

Wind and Water Penetration Testing

Testing to AS 2047.1 as per test method 4420.0 to .6

Manufacturer / Customer

Shanghai Superhouse Building Material Co Ltd

**Test Sample Data** 

**Deflection Ratio** 

180

Unit type	2 x Sliding Window				
Unit code	YYSD100				
Size	H (mm)	1300			
	W (mm)	1400			
Design Pa:	3000				

Tested For	Y/N	Rating	Units
Structural Deflection ?	Yes	3000	Pa
Air Infiltration ?	Yes	75/150	Pa
Operating Force Initial / constant ?	Yes	110/90	N
Water Penetration ?	Yes	300	Pa
Ultimate Strength ?	Yes	4500	Pa

**Test Unit Specifications** 

Results

	Sizes		н	w	Area sq m	Glass Type	Structural Framing Member	Span (mm)	Allowable Deflection	Deflection Result	Actual Ratio	Test Press (Pa)	Results
Frame			1300	1400	1.82		Interlock P	1070	5.94	1.37	781	3000	P
	Sash 1,2		1130	660	0.75		Interlock N	1070	5.94	2.88	372	3000	P
Sash							Mullion P						
							Mullion N						Г
	Thickne	ss (mm)	Н	W			Transom P						
	Sash 1,2	6-12-10	1017	569	0.58	Clear Float	Transom N						
Glass							H/L Trans P						Г
							H/L Trans N						Г
							H/L Mullion P						
							H/L Mullion N						
							Meet Style P						
							Meet Style N						
							Spare						
						- 1	Spare						

## **TESTING LABORATORY REPORT**

#### **Test equipments**

The test equipment and methods used in the above test comply with the requirements of AS 4420.1-6.

#### **Test Specimen**

See drawings at the end of this report.

#### **Test Methods**

The test unit was fixed into the rig as outlined in AS 4420.1.

#### **Deflection Test**

The unit was subjected to both positive and Negative pressure as prescribed in AS 4420.2. After the initial settling in of the unit at the 50% of the required test pressure, the differential pressure was then applied slowly until the nominated design pressure was reached in Positive. This process was then repeated for the Negative.

## **Results of Test**

The test unit satisfied the requirements of AS 2047.1 in both the positive and negative deflection at the nominated design pressure.

_									
( )	h	S	ρ	r۱	ıa	tı	റ	n	S

Observations		
NIL		

#### **Air Infiltration Test**

The test was first completely sealed against air leakage as per AS 4420.4 to determine the air leakage of the test rig. It was then subjected to 75 Pa of both positive and negative pressure, and 150 Pa of both negative and positive pressure. Differential pressures were recorded. The test unit was then unsealed and subjected to 75 Pa of both positive and negative pressure. Differential pressures were recorded and air leakage then calculated. The actual leakage of the test unit was then determined.

Barometric p	ressure (Pbar):	1010		rature (° C)	30	
		SEALED	UNSE	ALED		
Max Pressure				Negative		
(Pa)	Positive (Pa)	Negative (Pa)	Positive (Pa)	(Pa)		
75	10	5	154	179		
150	20	16	351	454		

Test Pressure	Pressure Direction	Building / Window Type	Allowable leakage flow L/s m <sup>2</sup>	Test results			
				ls <sup>-1</sup> m <sup>-2</sup> Positive	ls <sup>-1</sup> m <sup>-2</sup> Negative	Pos +	Neg -
75 Pa	+/-	Air conditioned	1.0	4.69	5.66	N/A	N/A
75 Pa	+	Non air conditioned	5.0	4.69	5.66	Passed	
150 Pa	+/-	Air conditioned	1.6	7.24	8.79	N/A	N/A
150 Pa	+	Non air conditioned	8.0	7.24	8.79	Passed	

# **TESTING LABORATORY REPORT**

# Results of test

The test unit satisfied the requirement of AS 2047. The test unit was tested to AS 4420.4. The net flow readings are as follows:

#### Observation

NIL		

# **Operating Force**

# **OPERATING FORCE (N)**

		Opening Force	Closing Force
Initiating Movement	Sash 1	45	22
Sustaining Movement	Sash 1	6	6
Initiating Movement	Sash 2	45	24
Sustaining Movement	Sash 2	6	6
Initiating Movement	Sash 3		
Sustaining Movement	Sash 3		

A force gauge was attached to the operating handle of the sash to determine the force required to set the sash in motion and thereafter to maintain motion as per AS 4420.3.

## Results of test

The test unit satisfied the requirement of AS 2047.

## **Observations**

NIL

# **TESTING LABORATORY REPORT**

# **WATER PENETRATION**

Water was applied to the exterior of the test unit with no less than 0.05 ls-1m-2 for a period of five minutes at zero pressure. After five minutes, a nominated pressure was applied for fifteen minutes as per AS 4420.5.

Maximum pressure (Pa) applied for 15 minutes (Nominated pressure)
---

300

#### **Results of test**

The test unit failed the requirement of AS 2047 in positive pressure at the nominated design pressure.

#### **Observations**

Silicone added to a	all framing jo	oints of box	section sub	frame.
---------------------	----------------	--------------	-------------	--------

#### **ULTIMATE STRENGTH TEST**


A pressure nominated on part 1 of this report and determined by AS 2047, table 2.5 was applied to the test unit for a period of 10 seconds as per AS 4420.6.


Max. pressure reached for 10 seconds				
Positive	Negative			
4500	4500			

Results of test:	Y or N	
Dislodgement of any glass?	No	
Dislodgement of a frame or any part of a frame?	No	
Removal of alignment with or without its framing sash from a frame?		
Loss of support of a frame such as when it is unstable in its opening in the building structure?	No	
Failure of any sash, locking device, fasteners or supporting stay which would allow an opening light to come open?	No	
The test unit satisfied the requirement of AS 2047.		

## **Observations**

0.000.144.01.0	
NIL	





\* SILICONE WINDOW SECTION TO FRAME \* SILICONE ALL FRAMING JOINTS (WINDOW + BOX)

Page 7 of 7